A light for Science





Maintenance and Reliability Workshop at SOLEIL - 9 and 10 November 2011 - Slide # 1



Maintenance and Reliability for facilties at the ESRF

Y Gouez - Electrical unit F Favier - HVAC unit T Marchial - Head of the BIG P Roux-Buisson - Maintenance Method

• The ESRF (European Synchrotron Radiation Facility)

The facilities at the ESRF

③ The maintenance contract for the facilities


4 The performance indicators

G Conclusion



O The ESRF








• • • The ESRF




Storage ring :844m roundElectrons :6 GeV

44 Beamlines




European Synchrotron Radiation Facility





Maintenance and Reliability Workshop at SOLEIL - 9 and 10 November 2011 - Slide # 5







• The ESRF (European Synchrotron Radiation Facility)

2 The facilities at the ESRF

O The maintenance contract for the facilities

OThe performance indicators

G Conclusion

European Synchrotron Radiation Facility



O The facilities

Main contracts (non-exhaustive list)

- Civil works
- Cleaning
- Landscaping
- Snow removal
- Waste management
- Cabling
- Electrical facility control
- Electricity supply
- Fan coil unit maintenance
- Piping maintenance
- Plumbing / sanitary maintenance
- Liquid nitrogen, gas nitrogen, liquid helium supply
 - Maintenance and operation for the infrastructures



The facilities

Equipment classification

Air handling system

Fluids

Electricity

European Synchrotron Radiation Facility



O The facilities Equipement : Classification

Level 1
 Cut-off leading to a beam loss (accelerator and source)

⇒Level 2
 ⇔ cut-off disturbing the users (beamlines and sectors)

⇒Level 3
♦ anything not Level 1 nor Level 2



O The facilities : HVAC and Fluids

 \sim \sim \sim \sim

Heating Ventilation Air Conditionning

- 90 air handling units (from 2 000 To 50 000m3/h)
- 160 exhaust vents
- 1 200 fan coil units
 - 160 pumps (from very few m3/h to 2 500m3/h)

<u>Fluids</u>

- 1 primary cooling network (29 000kW)
- 1 main cooling network (7 000kW) for the accelerator
- 3 secundary cooling networks (20 to 500kw)
- 1 main chilled water network (4 000kW) (HVAC system)
- 14 secundary chilled water networks (70 to 750kw)
 - 5 heating water networks (500 to 2 000kw)



The facilities : Electricity

Total annual consumption :65 GWHMaximum power for the subscription:11Mw

- 9 20kV/400 or 700VAC electrical substations
- 92 20KV high voltage cells
- 18 high voltage transformers (1000 to 2500 KVA)
- 80 UPS (uninterrupted power supply) (20 to 500KVA)
- 1 500 electrical cabinets and cupboards
 - 750 emergency lighting units
- 5000 lighting points





• The ESRF (European Synchrotron Radiation Facility)

The facilities at the ESRF

The maintenance contract for the facilities

OThe performance indicators

G Conclusion

European Synchrotron Radiation Facility



1. General presentation

2. Computerized maintenance management system: the « Heart of the control System »


3. Plan / Do / Check / Act : follow-up of actions

4. Example of reports





Maintenance contract for the facilities





Contract entrusted to a subcontractor :

- * 33 documents defining the services
- * 4-year contract, updated every year
- * About 950k€ per year (including the spares)


<u>2011 :</u>

- * 14 000 hours on-site works
- * 4 500 hours for administrative tasks
 - => 9 persons on-site
 - => occasional additional manpower

Not included in the contract :


- * main maintenance
- * regulatory check





European Synchrotron Radiation Facility






European Synchrotron Radiation Facility



Continuous improvement within the maintenance contract: Incident report and follow-up Improvement





Example of incident report (in French)



COMPTE RENDU D'INCIDENT N° CRI 11-025 Défaut variateur SRX1

| Rédigé par : | | Laurent PERRIN | Visa : | | |
|-------------------------|------------------------|--------------------|---------------------|--|--|
| | Diffusion Cegelec : | Equipe Maintenance | Diffusion ESRF : | Frédéric FAVIER Pascal ROUX BUISSON | |
| Suivi des modifications | | | Indice | Date | |
| Edition du document | | | A | 12/09/2011 | |
| | | | | | |



European Synchrotron Radiation Facility







Rapport d'incident N° 11-025 Défaut variateur SRX1 Indice A

Page 3/6

1. FACTS / STATEMENT / DESCRIPTION

Appel du 10/00/2011 à 20h35 Pour défaut réseau pompe SRX1 Armé aur site à 21h15 Vérification GTC, basculement sur l'autre pompe et paramètre SRX OK. Vérification de la présence tension. OK. Le ventilateur du variateur fonctionne. Étuée de la documentation. Reset du variateur en ocupart électriquement. La cate mère du variateur semble HS. Nécessaire sera fait lundi. Fin d'interrention à 28000.

2. IMMEDIATE CURATIVE ACTIONS

Le 12/09/2011 :

Consignation du variateur, dé-câblage et démontage. Mise en place et raccordement du variateur de spare (contrât rockwell). Ce variateur est sous garantie. Remise sous tension et programmation du variateur. Conditionrement du variateur le pour envoi chez ROCKWELL pour remplacement.

Le 13/09/2011 :

RI-11-025 Defaut variateur SRX1.doc

Lors du MDT :

Mise en service de l'interface de communicadon ISB ROCKWELL. Nos en service se statistice carro available Mise en service se casa du varialeur enci lest de la procédure de basculement sans coupure (nonctonnement perdant 11:80). Re-basculement sur la pompe SRX2 à 1618.0. Verification de deux varialeurs à la camirés themique.

DO

Rapport d'incident N° 11-025 Défaut variateur SRX1 Indice A

3. EXPLANATIONS / ANALYSES

Lors du démontage nous avons trouvé une connexion défectueuse sur une borne de sortie du variateur.



La mauvaise connexion du câble dans la borne a causé un échauffement et une rupture de la continuté. L'expertise de ROCWELL, nous permettra de savoir si cette rupture de connexion sur la puissance à un lien avec la perte de la commande du variateur.

La mise à disposition de pièces détachées dans le cadre du contrât ROCKWELL permet d'intervenir et de remettre en service rapidement les installations.

Un contrôle préventif à la caméra thermique sur les deux variateurs à été fait afin de repérer d'autre défaut de connexion.




RI-11-025 Defaut variateur SRX1.doc

Page 4/6

European Synchrotron Radiation Facility







Maintenance and Reliability Workshop at SOLEIL – 9 and 10 November 2011 – Slide #22



• The ESRF (European Synchrotron Radiation Facility)

The facilities at the ESRF

• The maintenance contract for the facilities

4 The performance indicators

G Conclusion

European Synchrotron Radiation Facility



Contract with obligation to produce specific results


Calculation of the annual indicator and financial consequences

Presentation of the various indicators

Conclusion after 4-year operation

European Synchrotron Radiation Facility







| Reference | Quaterly Indicator | | | | Reference | Annual Indicator | | Coe | |
|--------------------|--------------------|---|------|--------------|--------------------|---------------------|----------------------------|-----|--------------|
| Reference | Name | Designation | Coef | Basis 100 | | Name | Designation | f | Basis 100 |
| indicator 1 | 111 | Quality | 100 | • | Indicator IT | | Average of the Quaters | 50 | |
| | 112 | Work follow-up | 100 | | Indicator I20 | | Accelerator unavailability | 25 | |
| indicator 2 | 121 | N1 facility reliability | 100 | | Indicator I10 | | Proposals for improvement | 15 | |
| | 122 | N2 facility reliability | 100 | | Indicator 180 | | Management of spare parts | 10 | |
| indicator 3 | 131 | Management of N1 corrective intervention | 100 | | Total resulting | Annual Indicator I0 | | 100 | 100 |
| | 132 | Management of N2 corrective intervention | 100 | | | • | | - | |
| | 133 | Management of N3 corrective intervention | 100 | | | | | | |
| indicator 4 | 141 | Incident management - analysis | 100 | | | | | | |
| | 142 | Incident management - deadline | 100 | | | | | | |
| indicator 5 | 151 | Management of scheduled interventions | 100 | | | | | | |
| indicator 6 | 161 | Safety management | 100 | | | | | | |
| indicator 7 | 171 | Respect of the « mutual commitment » document | 100 | | | | | | |
| Total resulting | ΣIT (IT basis 100) | Total of the quaterly indicators | 1200 | 100 | | | | | |



CONSEQUENCES ON THE ANNUAL BALANCE SHEET

Annual indicator :

 $I0 = 100 - \Sigma$ reductions

Financial consequences: direct impact on the total amount of the contract

I0 < 85 : premium</td>5%I0 < 90 : premium</td>1.5%I0 < 95 : bonus</td>0% (based contract)I0 > 95 : bonus1%

Refund for the I0 evolution :

I0 evolution of N to N+1 period over 2% => 1% bonus



Respect of good engineering practice (I11)

Fault = -0.06% for a « Level 1 » installation

- = -0.04% for a « Level 2 » installation
- = -0.02% for a « Level 3 » installation

Respect of deadlines (I12 / 31 / 32 / 33 / 42 / 51)

- Delay = -0.06% for a « Level 1 » installation
 - = -0.04% for a « Level 2 » installation
 - = -0.02% for a « Level 3 » installation

Quality of the reports (I41 / 71)

- Non-quality = -0.06% for a « Level 1 » installation
 - = -0.04% for a « Level 2 » installation
 - = -0.02% for a « Level 3 » installation



Respect of safety rules (I61)

Incident with a work stoppage = -0.06%Any other breach of order = -0.04%

Proposals for improvement (I10)

Less than 4 proposals: - 3.75% per missing proposal

Management of spare parts / storage (180)

Inventory difference > 3 % : - 0.75 %

Inventory difference > 8 % : - 2.25 %

Inventory difference > 15% : - 15 %



Reliability and equipment availability (I20/21)

Level 1 or Level 2 equipment unavailability


- - 0.01% per hour of unavailability
- Up to 4% (400 hours) of unavailability
- Repaired equipment are part of this statement

Accelerator unavailability

- - 0.2% per hour of unavailability.
- Up to 20 % (100 hours) of unavailability



Example of non-compliancy data sheet



Example of indicator follow-up



• The ESRF (European Synchrotron Radiation Facility)

The facilities at the ESRF

• The maintenance contract for the facilities

OThe performance indicators

Conclusion



G Conclusion


CONCLUSION AFTER 4-YEAR OPERATION

A good method for communication

Well-accepted by the subcontractor

Possibility of bonus => enables a better acceptance from the intervening people / companies The indicators help for a better involvement of the subcontractors





European Synchrotron Radiation Facility

A light for Science



Thank You For Your Attention

Further Information

Should you have any question, do not hesitate

Feel free to visit our web site : www.esrf.eu

Maintenance and Reliability Workshop at SOLEIL – 9 and 10 November 2011 – Slide #35